

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR 25 W  
T 46 R R 26 W

~~EMMETT~~ Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 20, 24, 25

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER

7" W. Pine - N 97 W - 25 Links

9" W. Pine - N 52 E - 85 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. Rock Knobs, as per Gov't. Field Notes, South and West.

Corner was placed and witnessed November 10, 1953.

SURVEYORS SEAL

SIGNED Archie C. Seale DATE 9/2/54  
REGISTERED LAND SURVEYOR