

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR. 25 W.

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 9, 10, 15, and 16

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" J. Pine (S 10 NBT) N 8 E 41 Links

8" J. Pine (S 15 NBT) S 28 E 41 Links

6" J. Pine (S 16 NBT) S 34 W 23 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was reestablished from Section corner one mile south; Section corner 2 miles north; Fence 1/2 mile East; Section corner 1 mile west. Found no evidence of original corner. Found J. Pine tree reported by County Road Commission to be possible B. T. This tree is only 75 year old, not an original bearing tree.

Corner was placed and witnessed July 14, 1959.

SURVEYORS SEAL

SIGNED *Billy D. Buckler* DATE 4/11/60
REGISTERED LAND SURVEYOR
Billy D. Buckler