

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~4647~~ NR 25 W

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Section 3, 4, 33, 34.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 10" J. Pine (S 34 NBT) N 20° E 44 Links

5" W. Birch (S 33 NBT) N 86° W 21 Links

7" Aspen (S 3 NBT) S 50° E 15 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced at an old wood stake. Stake appears to be in line with E-W road 1/4 mile to East. No evidence of original corner.

Corner was placed and witnessed July 14, 1959.

SURVEYORS SEAL

SIGNED *Billy D. Buckler* DATE 4/11/60
REGISTERED LAND SURVEYOR
Billy D. Buckler