

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1999 DEC 22 AM 11:25

Patricia A. Hanley
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 46N R 25W A-8 ✓
T 46N R 26W M-8
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R2** PAGE 200
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on May 14, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-8: Corner common to Sections 19, T46N-R25W and 24, T46N-R26W.

1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:
8" Spruce S65E, 72L 4" Tamarack N30W, 13L

1990: Survey field notes by Sundberg, Carlson and Associates, Inc., indicates a set 5/8" by 18" iron rebar with a P.S.#24589 cap on it in a low lying area with tag alder, spruce, and tamarack trees referenced by:
5" Spruce S74W, 19.28' 11" Tamarack S41E, 37.75'
5" Spruce N72E, 33.48' 5" Spruce N17E, 18.88'

1994: An easement description map by Sundberg, Carlson and Associates, Inc., indicates a corner distance S00-08-08W, 2634.52' to the section corner common to Sections 19 and 30, T46N-R25W and Sections 24 and 25, T46N-R26W. No description or references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8: 1999: No original corner evidence found. Found and accepted a 5/8" P.S. #24589 capped iron 0.1' above ground.
Measured Line Call: North, 11.5 chains (759'), leave swamp, course W.- N.W. We measured 770'.
Measured Line Call: North, 14 chains (924'), top of knob. We measured 969'.
Measured Line Call: South, 9 chains (594'), enter swamp course E-W. We measured 563'.
Measured Line Call: South, 10.5 chains (693'), knob of granite rock 548.1 ft. We measured 678'.
Measured found reference:
6" Spruce S74W, 19.28'(dead) (SCA-1990)
Distance North is 2634.88', South is 2634.89'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8: 1999: Replaced the 5/8" X 18", P.S. #24589 capped iron with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner and referenced by:

Established new references:
6" Spruce S85W, 21.56' 6" Spruce N24W, 55.34'
5" Spruce N08E, 46.28' 5" Tamarack S10W, 39.73'

Green Steel Sign Post w/ Yellow Survey Marker Sign N32W, 3.8'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed
T46N-R25W Corner Search Sheet 99100

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Buasme
DATE 10/25/99



Signed by Gerald W. Carlson Date 12-8-99

Surveyor's Michigan License No. 24589