

1999 DEC 22 AM 11: 25

Patricia A. Manley
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: Corner Code #
(County)

1. Public Land Survey T 46N R 25W A-9 ✓
T 46N R 26W M-9
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R2** PAGE 201

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on May 14, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-9: Corner common to Sections 19 and 30, T46N-R25W and 24 and 25, T46N-R26W. 1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:
12" Spruce Pine S25E, 11L 11" Spruce Pine N47W, 19L
1845: William Ives' original subdivision survey notes of T46N-R25W, do not describe the corner. He adds the following references:
9" Spruce S43E, 23L 9" Spruce N47E, 49L

(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-9: 1999: No original corner evidence found. Found and accepted a 1 1/4" outside diameter iron pipe with 4" brass tablet on top projecting 1.1' above ground.

Checked Line Call: South, 17.8 chains (1174'), Stream 10L Course East, with a hip chain we measured 1275.00' to a dry stream bed. Distance North is 2634.89', South is 2641.71'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-9: 1999: Stamped the 1 1/4" outside diameter iron pipe with 4" brass tablet monument with: "MCR 1999". Monument is 1.1' above ground.

Measured found reference:
7" W. Pine N37W, 16.50' (Dept. Of Conservation) -dead
Established new references:
15" W. Pine N80W, 49.65' 7" Spruce N51W, 36.90'
5" Spruce N17W, 40.32' 9" Spruce N04W, 47.42'
Green Steel Sign Post w/ Yellow Survey Marker Sign S02E, 3.50'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.
T46N-R25W Corner Search Sheet 99100

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussome
DATE 10/25/99



Signed by Gerald Carlson Date 12-8-99
Surveyor's Michigan License No. 24589

A-9:

PART A CONTINUED:

1953: A Land Corner Record by the Michigan Department of Conservation, indicates a set 1" pipe with 4" brass cap. The Land Corner Record states: "This corner was established by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. Rock knobs, as per Gov't. Field notes, South and West. Corner was placed and witnessed November 10, 1953." Referenced by:
7" W. Pine N37W, 25L 9" W. Pine N52E, 35L

1989: Survey notes by Sundberg, Carlson and Associates, Inc., indicates they found a 1" iron pipe with a 3.5" diameter cap stamped by the Michigan Department of Conservation. No references given.

1990: A survey calculation sheet by Sundberg, Carlson and Associates, Inc., indicates the corner location distance N-00-08-08E, 5269.67 to the section corner common to Sections 18 and 19, T46N-R25W and Sections 13 and 24, T46N-R25W. It also indicates the corner distance S01-14-04W, 10,567.11' H to the township corner.

1990: Easement Description maps by Sundberg, Carlson and Associates, Inc., indicates a corner location. No description or references given.

1994: An Easement Description map by Sundberg, Carlson and Associates, Inc., indicates the corner position distance N00-08-08E, 2634.52' to the 1/4 corner common to Section 19, T46N-R25W and Section 24, T46N-R26W.

APP
R

SECTION

SECTION