

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1999 DEC 22 AM 11:25

Patricia L. Moulton REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION MARQUETTE (County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 25W A-11 T 46N R 26W M-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

LIBER R2 PAGE 203

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, GERALD W. CARLSON, in a field survey on May 20, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: A-11 Corner common to Sections 30 and 31, T46N-R25W and Sections 25 and 36, T46N-R26W.

1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by: 12" Spruce Pine S35E, 27L 10" Spruce Pine N29W, 13L

1845: William Ives' original subdivision survey notes of T46N-R25W do not describe the corner. He adds the following references: 12" Spruce Pine S37E, 27L 6" Fir N61E, 11L

(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11: 1999: No original corner evidence found. Found and accepted a 1 1/4" outside diameter galvanized iron pipe with a 4" aluminum tablet at West edge of power line clearing projecting 1.3' above the ground. Checked Line Call: South, Var. 5-15' on a rock or ledge, 6 chains (396'), with a hip chain. We measured 420' to a rock ledge. Checked Line Call: North, Granite Knob, 11 chains (726'), with a hip chain we measured 800' North and 90' East to a rock knob. Found: 10" White Pine S04W, 17.59' 15" White Pine N05E, 45.30' Distance North is 2641.31', South is 2641.48'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11: 1999: Stamped the 1 1/4" outside diameter galvanized iron pipe with a 4" aluminum tablet at corner with "MCR 1999". Monument was reset deeper so it is now 0.85' above ground. Measured found references: 10" White Pine S04W, 17.59' (Sackett NBT-1990) 15" White Pine N05E, 45.30' (Sackett NBT-1990)

Established new references:

10" Jack Pine S37W, 27.64' 6" Spruce N30W, 29.75' Green Steel Sign Post w/ Yellow Survey Marker Sign N73W, 2.89'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed. T46N-R25W Corner Search Sheet 99100

Grid table with columns A-M and rows 1-13. Cell 11,1 contains a black dot.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Larry J. Bussard DATE 10/25/99



Signed by Gerald W. Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589

A-11:

PART A CONTINUED:

MARQUETTE COUNTY
MICHIGAN
RECEIVED TO RECORD

1990: An LCRC recorded by Keith Sackett, P.S.# 19006, Liber 5 RC, Pg. 279, indicates he set a 1" inside diameter iron pipe 32" long with a 1" aluminum cap midway and on line. Original monument and accessories not found. He established the following references:

9" White Pine	S06W,	17.4'	S36	NBT
8" White Pine	S50E,	10.9'	S31	NBT
14" White Pine	N05E,	44.7'	S30	NBT

1994 DEC 22 AM 11: 25

Peterson A. Monkey
REGISTER OF DEEDS

1990: Field notes by Sundberg, Carlson and Associates, Inc., indicates a found corner. No monument description or references given.

1990: Easement description maps for Wisconsin Electric by Sundberg, Carlson and Associates, Inc., indicates a corner. No monument description or references given.

1990: A survey calculation sheet by Gerry Carlson, P.S. #24589, indicates a DNR monument at the corner location. A distance of N01-14-04E, 10,567.12' between the corner to the South and North is given.

1990: A survey reference map by Sundberg, Carlson and Associates, Inc., indicates a corner. No references or description are given.