

RF

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1999 DEC 22 AM 11:25

Patricia L. Manley REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE (County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 25W B-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

LIBER R2 PAGE 205 Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on October 27, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: B-1 North Quarter Corner Section 6, T46N-R25W, 1999: Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1: 1999: Corner position established by single proportionate measurement between the Northwest and Northeast corners of Section 6 on line between the South quarter corner and the Southwest corner of Section 31, T47N-R25W. Distances are 2474.16' West and 2636.29' East along the North Township Line of T46N-R25W to the Northwest and Northeast corners of Section 6. The South quarter corner of Section 31, T47N-R25W is East 23.74'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.25' above ground. Referenced by:

- 9" Jack Pine N05W, 16.21' 8" Jack Pine N88E, 12.32'
10" Jack Pine S42E, 45.93' 7" Jack Pine S71W, 13.52'
S 1/4 Section 31, 47-25 SC, N89W, 23.73'

Green Steel Sign Post w/ Yellow Survey Marker Sign N11W, 2.09'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed. Bk. 12, Pg. 134 T46N-R25W Corner Search Sheet 99100

Grid table with columns A-L and rows 1-13. Cell B1 contains a black dot.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Larry J. Bussard DATE 11/1/99



Signed by Gerald W. Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589