

1994 DEC 28 PM 5:59

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 94030

SHEET NO. : 1-534

For corners in

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 25W	B-1
	T 46N R 25W	B-13 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Patricia A. Manley
REGISTER OF DEEDS

LIBER 1 PAGE 200
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Tuesday, December 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1: Quarter Corner common to Section 6, T45N-R25W and Section 31, T46N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
5" Spruce N62E, 22 1
4" Spruce N32W, 37 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994- No original evidence found. C. Cummings in 1909 did not indicate any original evidence at this corner position as he ran the North line of Section 6 from the B.T. Corner at the NW Corner of Section 6 to the B.T. Corner at the NE Corner of Section 6. Set the corner proportionately on line between the NW and NE Corners of Section 6. SCA distance between section corners is 5171.27' as compared to the GLO distance of 5184.96' which is 13.69' short. Cummings mile distance is 5172'. DNR calculated mile distance is 5173.30'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Buason
DATE Sept 26, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 3/4" by 5' long iron capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
4" Black Spruce N20E 12.59 ft.
5" Tamarack N56E 18.08 ft.
5" Tamarack S29E 17.43 ft.
4" Black Spruce S74W 15.30 ft.
Steel sign post North 1.6 ft.
Monument is 0.2' above ground and is set in a Black Spruce and Tamarack swamp roughly 950' North of a woods road.
Bk. 6, Pg 139

Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JUNE 27, 1971
24589 REVISED MAY 27, 1975
REVISED OCT., 1983

