

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD

1999 DEC 22 AM 11: 25

*Patricia A. Manley*  
 REGISTER OF DEEDS

LIBER **R 2** PAGE **207**

Register of Deeds Stamp & File Number

For corners in MARQUETTE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 46N R 25W \_\_\_\_\_ D-1  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on October 28th, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
 D-1: North Quarter Corner Section 5, T46N-R25W.  
 1999: Not part of original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 D-1: 1999: Corner position established by single proportionate measurement between the Northwest and Northeast corners of Section 5, on line between the Southwest corner of Section 32 and the South quarter corner of Section 32, T47N-R25W. Distances are 2635.64' West and 2635.64' East along the North Township Line of T46N-R25W to the Northwest and Northeast corners of Section 5. The South quarter corner of Section 32, T47N-R25W is East 24.42'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 D-1: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.25' above ground. Referenced by:

Green Steel Sign Post w/ Yellow Survey Marker Sign NOE, 2.2'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.  
 Bk. 12, Pg. 132 T46N-R25W Corner Search Sheet 99100

	A	B	C	D	E	F	G	H	I	J	K	L	M
1				●									
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**

*Larry J. Buzzard*  
 DATE 11/1/99

SECTION



Signed by Gerald W. Carlson Date 12-8-99  
 Surveyor's Michigan License No. 24589