

1999 DEC 22 AM 11: 25

Patricia A. Hanley
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: Corner Code #
(County)

1. Public Land Survey T 46N R 25W E-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

LIBER **R2** PAGE **208**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on October, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: Corner common to Sections 4 and 5, T46N-R25W on the North Township Line.
1845: William Ives original subdivision survey notes describe the corner monument as a wood post 38 links West of the corner to Sections 32 and 33, T47N-R25W referenced by:
9" Spruce Pine S10E, 13L 4" Spruce Pine S77W, 34L

1953: A Land Corner Record by Dean Delameter of the Michigan Department of Conservation, indicates he set a 1" pipe with a 4" brass cap referenced by:
4" Jack Pine N67E, 12 links.

He states: "This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. North to Summit of Hill, West to Rock Knob, South to original B.T.'s."

1990: A section breakdown sheet by Gerry Carlson, P.S.#24589, indicates the corner location distance S89-35-27E, 25.08' to the section corner of Sections 32 and 33, T47N-R25W and distance S89-55-38W, 7907.34' to the North quarter corner of Section 5, T46N-R25W.

1990: An easement description map for Wisconsin Electric indicates the corner. No description or references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1: 1999: No original corner evidence found. Corner position was established 25.08' West of the Southeast corner of Section 32, T47N-R25W, and on line between the Southeast corner and the South quarter corner of Section 32, T47N-R25W. Distance West is 2635.64', East is 2629.99'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.10' above ground. Referenced by:

14" Jack Pine N88E, 32.94' 9" Twin Birch S81W, 54.74'
6" Maple Cluster N07E, 122.44' 8" Jack Pine S66E, 81.28'
S.E. Cor. Section 32, 47-25 (sc) S88E, 25.08'

Green Steel Sign Post w/ Yellow Survey Marker Sign S07E, 2.76'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 12, Pg. 142 46-25 Corner Search Sheet 99100

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Busone
DATE 11/1/99

Signed by Gerald Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589

