

1999 DEC 22 AM 11:25

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in MARQUETTE
(County)

Located In: Corner Code #

1. Public Land Survey T 46N R 25W F-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Peterson R. Stanley
REGISTER OF DEEDS

LIBER **R2** PAGE 209
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on October, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1: North Quarter Corner of Section 4, T46N-R25W.
1999: Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1: 1999: Corner position established by single proportionate measurement between the Northwest and Northeast corners of Section 4 on line between the South quarter corner and the Southwest corners of Section 33, T47N-R25W. Distances are 2629.99' West and 2629.99' East along the North Township Line of T46N-R25W to the Northwest and Northeast corners of Section 4. The South quarter corner of Section 33, T47N-R25W is East 27.06'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.10' above ground. Referenced by:

12" Twin Oak	S71E,	42.16'	11" Twin Oak	N11W,	57.23'
14" Jack Pine	S34W,	56.48'	11" Jack Pine	S09E,	31.31'
S 1/4 Section 33 47-25 (sc)	S89E,	27.06'			

Green Steel Sign Post w/ Yellow Survey Marker Sign S10W, 2.65'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 12, Pg. 90 T46N-R25W Corner Search Sheet 99100

Bk. 12, Pg. 144

	A	B	C	D	E	F	G	H	I	J	K	L	M
1						●							
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP

P.A. 345 OF 1990

Larry J. Bussone
DATE 11/1/99



Signed by Gerald W. Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589