

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1999 DEC 22 AM 11:25

Patricia A. Moulton
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 46N R 25W _____ G-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R 2** PAGE **210**
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on November 11th, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-1: Corner common to Sections 3 and 4, T46N-R25W on the North Township line.
1845: William Ives original subdivision survey notes describe the corner monument as a wood post 44 links West of corner of sections 33 and 34 T47N-R25W referenced by:
9" Spruce Pine S09W, 15L 8" Spruce Pine S27E, 36L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-1: 1999: No original corner evidence found. Corner position was established 29.04' West of the Southeast corner of Section 33, T47N-R25W on line between the Southeast corner and the South quarter corner of Section 33, T47N-R25W. Distance West is 2629.99', East is 2646.42'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-1: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is flush with the ground. Referenced by:
10" White Birch N88E, 15.65' 10" Oak N40E, 51.69'
7" Maple S26E 77.60' 12" Spruce S40E, 20.00'
S.E. Cor. Section 33, 47-25 (sc) S87E, 29.04'
Green Steel Sign Post w/ Yellow Survey Marker Sign N14E, 3.09'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.
Bk. 12, Pg. 146 T46N-R25W Corner Search Sheet 99100

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Busone
DATE 11/1/99



Signed by Gerald W. Carlson Date 12-8-99
Surveyor's Michigan License No. 24589