

SURVEY & REMONUMENTATION

MAR 13 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1997 DEC 26 PM 12:46

Richard D. Manley
REGISTER OF DEEDS

For corners in **SECTION**

MARQUETTE

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------|--------------------|------------|
| 1. Public Land Survey | | <u>T.46N R.25W</u> | <u>G-8</u> |
| | | T_____R_____ | _____ |
| | | T_____R_____ | _____ |
| | | T_____R_____ | _____ |
| 2. Property Controlling in Section | S_____ | T_____R_____ | _____ |
| | S_____ | T_____R_____ | _____ |
| 3. Miscellaneous Property in Sec. | S_____ | T_____R_____ | _____ |
| | S_____ | T_____R_____ | _____ |

LIBER

2 PAGE 28

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on JUNE 11TH, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-8: Quarter Corner common to Sections 21 and 22.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:

8" Spruce Pine N85E, 36 L 6" Spruce Pine S21W, 23 L

1945: Survey field notes from M.C.R.C. F.B. #697, pg. 63, indicate the corner as a set 1" iron pipe and jack pine post referenced by:

7" J. Pine N35W, 4.0' 5" J. Pine S38E, 13.6'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 22) indicates the corner as a 1" Iron Pipe and Jack Pine Post referenced by:

7" J. Pine N35W, 4.0' 5" J. Pine S38E, 13.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8: 1997: No original corner evidence found. Found and accepted a 1/2" I.D. (1" O.D.) X 36" Pipe painted orange, 0.75' high. Found existing references as described in Part C below. There were no nearby line calls to check. Distance North is 2630.31' and distance South is 2626.09'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8: 1997: Replaced found Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.15' above ground. Measured found references:

10" J. Pine (Stump) N35W, 3.89' (to nail in butt blaze of stump) (M.C.R.C. NBT)
7" J. Pine S39E, 13.65' (to nail in butt blaze) (M.C.R.C. NBT)

Established new references:

6" J. Pine N17E, 42.28' (to set d.h. nail)
10" J. Pine N47E, 70.65' (to set d.h. nail)
10" J. Pine N76E, 35.26' (to set d.h. nail)
6" J. Pine S85E, 51.35' (to set d.h. nail)

Green Steel Sign Post w/ Yellow Survey Marker Sign N85W, 1.08'

Note: Found bearing trees have butt blaze with nail. New bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussane
DATE 12/8/97



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589