

SURVEY & REMONUMENTATION

MAR 13 1998

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1997 DEC 26 PM 12:46

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: Corner Code #
(County)

1. Public Land Survey T 46N R 25W G-9
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Patricia A. Manley
REGISTER OF DEEDS *pm*

LIBER 2 PAGE 29
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JUNE 12TH, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9: Section Corner common to Sections 21, 22, 27, and 28.
1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:
8" Spruce Pine S45E, 43 L 9" Spruce Pine N54W, 35 L

1941: Survey field notes from M.C.R.C. F.B. #712 (no pg. #'s given) indicate that a

1" Iron Pipe and two N.B.T.'s were set for the corner, but the corner was later moved and N.B.T.'s remeasured after calculations on the bearing between the S.E. Corner of section 34 and the N.E. Corner of Section 15 made it necessary to move the corner S71°19'E, 17.5' to correspond with errors in the U.S. Government Survey. Reset 1" Iron pipe and referenced as follows:

7" J. Pine N50W, 56.4' 14" J. Pine S33W, 33.8'

Note: Field sketch shows Distance, S89°38'E, 5318.2' to the N.E. Corner of Section 27. Distance, N89°38'W, 5257.6' to the N.W. Corner of Section 28.

1945: Survey field notes from M.C.R.C. F.B. #697, pp. 45-50 indicate that the corner was occupied as part of a traverse, and is described as an Iron Pipe. No accessories given.

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 28) indicates the corner as an Iron Pipe referenced by:
7" J. Pine N50W, 56.4' 14" J. Pine S33W, 33.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9: 1997: No original corner evidence found. Found and accepted a 3/4" I.D. (1-1/4" O.D.) Pipe painted orange leaning South to Southwesterly, 0.9' high. Found existing references as described in part C below. There were no nearby line calls to check. Distance North is 2626.09', distance South is 2631.52' and distance East is 2663.81'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9: 1997: Replaced found 3/4" I.D. (1-1/4" O.D.) Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.15' above ground. Measured found reference:

- 7" J. Pine (stump) N50W, 56.59' (to C/L) (M.C.R.C. NBT)
- 15" J. Pine S42E, 34.66' (to Set d.h. nail) (34.1' to butt blaze) (Possible M.C.R.C. NBT)
- Established new references:
- 9" J. Pine N87E, 73.25' (to set d.h. nail)
- 9" J. Pine S83E, 59.02' (to set d.h. nail)
- 8" J. Pine S15E, 34.39' (to set d.h. nail)

Green Steel Sign Post w/ Yellow Survey Marker Sign N77E, 1.25'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589