

MAR 13 1998

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 46

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 46N R 25W _____ G-10
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Patricia A. Mosley
REGISTER OF DEEDS

LIBER **2** PAGE **30**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JUNE 18TH, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10: Quarter Corner common to Sections 27 and 28.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:

6" Spruce Pine S11E, 30 L 6" Spruce Pine N81W, 10 L

1945: Survey field notes from M.C.R.C. F.B. #697, Pg. 50, indicate the corner as a set Iron Pipe and Jack Pine Post referenced by:

5" J. Pine N21E, 18.8' 5" J. Pine N70E, 42.6'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec's. 27 and 28) indicates the corner as an Iron Pipe and J. Pine Post referenced by:

5" J. Pine N21E, 18.8' 5" J. Pine N70E, 42.6'

No Date: The corner is indicated on a sketch of Co. Rd. 553 R.O.W. recorded in L. 90, MR Pg. 87. No description of corner object or accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10: 1997: No original corner evidence found. Found and accepted a 1/2" I.D. X 36" Pipe painted orange, 1.0' high.

Found existing references as described in Part C below. There were no nearby line calls available to check.

Distance North is 2631.52' and distance South is 2629.99'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10: 1997: Replaced found 1/2" I.D. X 36" Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.20' above ground. Measured found references:

12" J. Pine (stump) N20E, 18.87' (to C/L) (M.C.R.C. NBT)

14" J. Pine (stump) N67E, 42.75' (to C/L) (M.C.R.C. NBT)

Established new references:

5" J. Pine N81W, 25.77' (to set d.h. nail)

8" J. Pine S45W, 56.40' (to set d.h. nail)

5" J. Pine S20E, 76.86' (to set d.h. nail)

4" J. Pine S60E, 49.60' (to set d.h. nail)

Green Steel Sign Post w/ Yellow Survey Marker Sign S85W, 1.22'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE 12/8/97



Signed by Gerald W. Carlson Date 12-18-97

Surveyor's Michigan License No. 24589