

MAR 13 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 46

*Patricia R. Monney*  
REGISTER OF DEEDS

For corners in MARQUETTE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 46N R 25W \_\_\_\_\_ G-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LIBER **2** PAGE **31**  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JUNE 18TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
**G-11: Section Corner common to Sections 27, 28, 33, and 34.**

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:  
6" Spruce Pine S33W, 22 L 6" Spruce Pine N69E, 26 L

1945: Survey field notes from M.C.R.C. F.B. #697, Pg. 50 indicate the corner as a set Iron Pipe and Jack Pine Post referenced by:  
5" J. Pine S57W, 53.7' 6" J. Pine S73W, 25.1'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 28) indicates the corner as an Iron Pipe and Jack Pine Post referenced by:  
5" J. Pine S57W, 53.7' 6" J. Pine S73W, 25.1'

1948: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 27) indicates the corner as an Iron Pipe with new B.T.'s set:  
6" J. Pine N32W, 47.1' 7" J. Pine S65W, 25.3'

No Date: A Right of Way sketch for Co. Rd. 553 recorded in L. 90, MR Pg. 87 indicates the corner. No description of corner object or accessories given.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
**G-11: 1997:** No original corner evidence found. Found and accepted a 1/2" I.D. X 36" Pipe 0.8' high with orange paint. Found existing witnesses as described in Part C below. There were no nearby line calls available to check. Distance North is 2629.99', distance South is 2624.47' and distance East is 2625.08'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
**G-11: 1997:** Replaced found 1/2" I.D. X 36" Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is flush with ground. Measured found references:  
10" J. Pine N32W, 46.99' (to set d.h. nail) (M.C.R.C. NBT)  
13" J. Pine S65W, 24.81' (to set d.h. nail) (M.C.R.C. NBT)  
Established new references:  
8" twin J. Pine S11E, 41.66' (to set d.h. nail)  
10" J. Pine N06W, 35.95' (to set d.h. nail)  
Green Steel Sign Post w/ Yellow Survey Marker Sign N00E, 1.25'  
Note: Found bearing trees had scribed butt blazes. All Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**  
*Larry J. Bussone*  
DATE 12/8/97



Signed by Gerald W. Carlson Date 12-18-97