

**SURVEY & REMONUMENTATION**

MAR 13 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 46

**SECTION**

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 46N R 25W      G-12  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Patricia A. Manley*  
REGISTER OF DEEDS

LIBER **2** PAGE **32**  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on DECEMBER 9TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33	●	34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

**G-12:** Quarter Corner common to Sections 33 and 34.  
 1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:  
 5" Spruce Pine S73E, 09 L      4" Spruce Pine N42W, 04 L

No Date: The corner is indicated on a Right of Way sketch for Co. Rd. 553. No description of corner object or accessories given.

No other corner information available.

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**

*Larry J. Bussone*  
DATE 12/15/97

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**G-12: 1997:** No original corner evidence found. No other corner evidence found. Re-established Corner position mid way and on line between the S.W. Corner of Section 34 and the N.W. Corner of Section 34. There were no nearby line calls available to check. Distance North is 2624.47' and distance South is 2624.57' (As-staked distances).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**G-12: 1997:** Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is flush with ground and is 20' East of meandering tree line of 5" to 14" J. Pines. Established new references (measurements to set d.h. nails):

- 9" J. Pine      S03E,      48.27'
- 12" J. Pine     S30W,      42.43'
- 11" J. Pine     N67W,      28.69'
- 9" J. Pine      N27W,      28.25'

Green Steel Sign Post w/ Yellow Survey Marker Sign      N40E,      2.0'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.  
 Bk. 13, Pg. 21-22



Signed by Gerald W. Carlson Date 12-18-97

Surveyor's Michigan License No. 24589