

MAR 13 1998

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 DEC 26 PM 12: 46

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>46N</u> R <u>25W</u> | <u>H-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Patricia A. Manley
REGISTER OF DEEDS

LIBER **2** PAGE **33**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on AUGUST 6TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5								●					
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-5: Quarter Corner common to Sections 10 and 15.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:
6" Spruce Pine S71W, 13 L 8" Spruce Pine N38E, 18 L

1932: Survey field notes from M.C.R.C. F.B. #557, Pg. 19, indicate the corner as a set Fence Corner. Notes also indicate that they found a tree nearby with old blazes on East and West sides, evidently an old line tree. No accessories given.

1989: Survey field notes from the records of Gerald W. Carlson P.S. # 24589 indicate the corner as a set 5/8" rebar with cap #24589 referenced by:

13" J. Pine N89E, 2.45' 8" J. Pine S04E, 21.12'
Power Pole S44W, 60.87' 4" J. Pine N77W, 58.29'

RATIFIED BY PEER GROUP.
P.A. 345 OF 1990

Larry J. Bussard
DATE 12/8/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5: 1997: No original corner evidence found. Found and accepted a 5/8" Rebar with G. Carlson Cap #24589 215' North of Station Rd. and 22' East of C/L driveway House #200. Found existing references as described in Part C below. there were no Nearby line calls available to check. Distance West is 2637.18' and distance East is 2637.33'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5: 1997: Replaced found 5/8" Rebar with G. Carlson Cap #24589 with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is located 215' North of Station Rd. (Co. Rd. NB) and 22' East of Driveway for House #200. Measured existing references:

14" J. Pine N71E, 2.45' (to fd. nail) (Carlson NBT)
8" J. Pine S02E, 21.11' (to fd. nail) (Carlson NBT)
Power Pole S45W, 60.81' (to fd. nail) (Carlson Accessory)
7" Dying J. Pine N77W, 58.28' (to fd. nail) (Carlson NBT)

Established new Reference:

6" J. Pine N19W, 11.65' (to set d.h. nail)
Green Steel Sign Post w/ Yellow Survey Marker Sign North, 2.00'

Note: Stamped B.T. Tags were affixed to existing bearing trees which already had face and nail blazes. New bearing tree has painted face, butt, and side nail blazes, d.h. measuring nail, and stamped B.T. Tag affixed.

Bk. 9, Pages.123 & 128- 132



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589