

MAR 13 1998

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1997 DEC 26 PM 12:46

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 46N R 25W H-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Patricia A. Manley REGISTER OF DEEDS

LIBER 2 PAGE 34 Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JUNE 19TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7: Quarter Corner common to Sections 15 and 22.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:

4" Spruce Pine S20E, 07 L 8" Spruce Pine N41E, 32 L

1944: Survey field notes from M.C.R.C. F.B. #712 (No pg. # given) indicate the corner as a set 1" Iron Pipe and Jack Pine Post. Established references with tacks in blazes on:

6" J. Pine S23W, 55.6' 4" J. Pine N20W, 40.8'

(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7: 1997: No original corner evidence found. Found and accepted a 1 1/4" O.D. Pipe with a 3 3/4" diameter Aluminum Cap, 0.5' above ground, and stamped to identify the corner by Paul Bressette P.S. #37270 in 1993. Found references as described in Part C below. Checked Line Call: Distance West is 2630.62' and distance East is 2631.15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7: 1997: Stamped "MCR 1997" on found aluminum cap and painted exposed pipe orange. Measured found scribed reference trees with distances to found measuring notches and set d.h. nails:

- 9" J. Pine N04W, 39.77'(d.h. nail), 39.54'(meas. notch) (Bressette NBT)
7" J. Pine N89E, 26.86'(d.h. nail), 26.39'(meas. notch) (Bressette NBT)
6" J. Pine S01W, 16.12'(d.h. nail), 16.03'(meas. notch) (Bressette NBT)
10" J. Pine N82W, 35.26'(d.h. nail), 34.74'(meas. notch) (Bressette NBT)

Additional found references:

15" J. Pine S17W, 55.77' (to set d.h. nail) (MCRC NBT)

Found a squared scribed pine post next to corner (loose and painted red).

Orange Steel Sign Post w/ Yellow Survey Marker Sign S49E, 1.23'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 9, Pg.121

Grid table with columns A-M and rows 1-13. A dot is present at row 7, column H.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Larry J. Bussme DATE 12/8/97



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589

H-7:

**PART A CONTINUED:**

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 22) indicates the corner as a 1" Iron Pipe and jack Pine Post referenced by:  
6" J. Pine            S23W,    55.6'            4" J. Pine            N20W,    40.8'

1980: The corner is indicated as a found corner on a survey map of the S.W. 1/4 of Section 15 by Gourdie, Fraser, and Associates. Distance S89-06'-24"W, 2632.21' to the S.W. Corner of Section 15. No description of corner object or accessories given.

1993: An LCRC recorded by Paul R. Bressette P.S. #37270 in L. 5, RC Pg. 379 indicates the corner as a found Iron Pipe and S.W. Bearing Tree as described by the M.C.R.C. F.B. #712. All blazes on bearing tree were completely closed. He replaced the found Pipe with a D.N.R. Monument and referenced it as follows:

9" J. Pine	N06E,	39.55'	7" J. Pine	S83E,	26.35'
6" J. Pine	S07W,	16.05'	10" J. Pine	N82W,	34.75'