

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 46

Patricia A. Monley
REGISTER OF DEEDS

For corners in
MARQUETTE
(County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 25W H-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LIBER **2** PAGE **35**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JUNE 12TH, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-9: Quarter Corner common to Sections 22 and 27.
 1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:
 3" Spruce Pine S26E, 05 L 4" Spruce Pine N64W, 06 L

1945: Survey field notes from M.C.R.C. F.B. #697, Pg. 63, indicate the corner as a set Iron Pipe and Jack Pine Post referenced by:
 9" J. Pine S21W, 23.9' 10" J. Pine N72W, 27.3'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 22) indicates the corner as an Iron Pipe and Jack Pine Post referenced by:
 9" J. Pine S21W, 23.9' 10" J. Pine N72W, 27.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-9: 1997: No original corner evidence found. Found and accepted a 1/2" I.D. X 36" Pipe, 1.2' above ground, with old paint and flagging. Also found 2 witness trees as described in Part C below. Checked Line Call: Did not measure distance (West, 5.63 chains [371.58'], 4" Spruce Pine) as entire area has been altered by man (logged) since the original survey. Distance West is 2663.81' and distance East is 2682.78'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-9: 1997: Replaced found pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.1' above ground. Measured existing references:
 15" J. Pine S21W, 24.21 (to C/L); 24.04' (to set d.h. nail) (MCRC NBT)
 16" J. Pine N72W, 27.52' (to d.h. nail at C/L) (MCRC NBT)
 Established new references:
 14" J. Pine N01W, 49.90' 7" J. Pine N87E, 22.36'
 Orange Steel Sign Post w/ Yellow Survey Marker Sign S75E, 1.47'
 Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Leona J. Buswell
 DATE 12/8/97



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589