

MAR 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 47

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>46N</u> R <u>25W</u> | <u>H-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Patricia A. Manley
REGISTER OF DEEDS

LIBER 2 PAGE 36
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on December 9, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11: Quarter Corner common to Sections 27 and 34.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:

6" Spruce Pine N16E, 13 L 5" Spruce Pine S50W, 23 L

1945: Survey field notes from M.C.R.C. F.B. #697, Pg. 51, indicate the corner as a set Iron Pipe and Jack Pine Post referenced by:

7" J. Pine S69E, 18.7' 4" J. Pine N29W, 29.5'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 27) indicates the corner as an Iron Pipe and J. Pine Post referenced by:

7" J. Pine S69E, 18.7' 4" J. Pine N29W, 29.5'

No Date: The corner is indicated on a right of way sketch for Co. Rd. 553. No description of corner object or accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11: 1997: No original corner evidence found. Found and accepted a 1" O.D. Pipe bent slightly North. Found Pipe was painted red and blue and was 0.5' above ground. Found two existing references as described in Part C below. There were no nearby line calls available to check. Distance West is 2625.08' and distance East is 2626.22'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11: 1997: Replaced found 1" O.D. Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument was set at bend point of found 1" O.D. Pipe and is flush to ground. Measured existing references:

7" J. Pine (stump) S69E, 18.7' (M.C.R.C. NBT)
4" J. Pine (stump) N29W, 29.5' (M.C.R.C. NBT)

Established new references (distances are to set d.h. measuring nails).

4" J. Pine N60W, 74.50'
4" J. Pine N35W, 47.00'
4" J. Pine N14W, 58.13'
4" J. Pine N27E, 26.88'

Green Steel Sign Post w/ Yellow Survey Marker Sign: S30E, 2.0'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 13, Pgs.17-20

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Buasme
DATE 12/15/97



Signed by Gerald W. Carlson Date 12-18-97