

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1994 DEC 28 PM 5:59

JOB NUMBER: 94030
SHEET NO. : 1-540

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 25W T 46N R 25W T _____ R _____ T _____ R _____	H-1 H-13 ✓
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Patricia A. Monley
REGISTER OF DEEDS *pm*

LIBER 1 PAGE 206
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Sunday, December 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1: Quarter Corner common to Section 3, T45N-R25W and Section 34, T46N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a 8" diameter S. Pine referenced by: 9" S. Pine N44E, 27.1	1941: M.C.R.C. F.B. 712 indicates a set 1" iron pipe and J. Pine post and set new B.T.'s. Distances shown in F.B. 712 (5281.6') indicate set proportionately on line between the N.W. Corner of Section 3 and the N. Quarter Corner of Section 1. New B.T.'s: 5" J. Pine N81E, 63.0' 5" J. Pine S60W, 33.4'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994- Found and accepted iron pipe as set by M.C.R.C. in 1941. Distance East to North East Corner Section 1 is 13190.06' and distance West is 2639.60' as compared to 2640.80' (M.C.R.C.-1941).

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE Sept 26, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced 1" diameter iron pipe with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 8" Jack Pine N13E 19.85 ft. GCVN NBT
- 8" Jack Pine S62W 33.56 ft. GCVN NBT
- 7" Jack Pine N60W 205.10 ft.
- Top of 6' tall gas line marker N83E 105.45 ft.
- Steel sign post North 2.0 ft.
- Monument is 0.2' above ground in clear cut area 150' +/- West of the West edge of pavement of County Road 553
- Bk. 6, Pg. 125

Signed by Gerald W. Carlson Date 12-22-94
Surveyor's Michigan License No. 24589

