

MAR 13 1998

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1997 DEC 26 PM 12: 47

For corners in  
MARQUETTE  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 25W I-5  
T      R       
T      R       
T      R
- 2. Property Controlling in Section S      T      R       
S      T      R
- 3. Miscellaneous Property in Sec. S      T      R       
S      T      R
- 4. Lot No.         , Recorded Plat
- 5. Private Claims

*Patricia A. Manley*  
REGISTER OF DEEDS

LIBER **2** PAGE **37**  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on AUGUST 7TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**  
I-5: Section Corner common to Sections 10, 11, 14, and 15.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:  
8" Aspen S55E, 61 L 8" Aspen N25E, 33 L

1910: Charles Cummings, in Record of Surveys, Book 1, pp. 121-123, indicates that he used the corner during a survey of T46N-R25W. No description of corner object or accessories given.

1932: Survey field notes from M.C.R.C. F.B. #557, Pg. 19 indicate the corner is near the intersection of township roads. No description of corner object or accessories given.

1941: Survey field notes from M.C.R.C. F.B. #712 (no pg. # given) indicate a traverse into the corner, and that it is at the intersection of roads. No description of corner object or accessories given.

1970: A Survey Map recorded by Allen Heikkinen P.S. #6517 in L. 287, Deeds Pg. 253; and L. 289, Deeds pp. 6, 8, and 10, indicates the corner at the C/L intersection of Co. Rd. NT and Co. Rd. 553. No description of corner object or accessories given.  
(SEE REVERSE SIDE)

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**

*Larry J. Bussone*  
DATE 12/8/97

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-5: 1997: No original corner evidence found. Found and accepted a 3/4" X 6" Boat Spike on the C/L of Taylor Rd. (Co. Rd. NT) 20' East of C/L Co. Rd. 553. Found existing references as described in Part C below. There were no nearby line calls available to check. Distance West is 2637.33', distance East is 2587.10' and distance South is 2623.65'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-5: 1997: Replaced found Boat Spike with a 3/4" diameter x 3' long Rebar capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is in a monument box at the C/L of Taylor Rd. (Co. Rd. NT) 20' East of Co. Rd 553. Measured found references:

- 18" J. Pine N82E, 88.51' (to nail w/shiner) (Carlson NBT)
- Power Pole S64E, 75.79' (to nail w/shiner) (Carlson Accessory)
- Power Pole S75W 97.28' (to nail w/shiner) (Carlson Accessory)

Established new references:

- 7" Balsam N39W, 119.64' (to set d.h. nail)
- 9" J. Pine N33E, 77.54' (to set d.h. nail)
- 14" J. Pine S46E, 78.45' (to set d.h. nail)

Green Steel Sign Post w/Yellow Survey Marker Sign N64E, 61.6'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 9, Pg.133



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589

**PART A CONTINUED:**

1974: A sketch of Co. Rd. NNA (To be abandoned) recorded in L. 87, MR Pg. 554, indicates the corner at the intersection of Co. Rd. 553 and Co. Rd.'s. NT/NB. No description of corner object or accessories given.

No Date: Road construction plans (source unknown) indicate the corner at the C/L intersection of Co. Rd. NT/NB and Co. Rd. 553. No description of corner object or accessories given.

1980: An LCRC recorded by William R. Donnan P.S. #17618 in L. 4, RC Pg. 31 indicates the corner as a found R.R. Nail #59 in the center of Co. Rd. 553. Referenced by:

6" J. Pine	S50E,	78.52'	Light Pole	S51W,	40.60'
10" Twin W. Birch	N68W,	78.50'			

1983: A Mortgage Report by Gerald W. Carlson P.S. #24589 indicates the corner at the C/L Co. Rd. NT. No description of corner object or accessories given.

1989: Survey field notes from the records of Gerald W. Carlson P.S. #24589 indicates the corner as a found Boat Spike located near the intersection of Co. Rd. 553 and Co. Rd. NT/NB. Referenced by:

15" J. Pine	N79E,	88.55'	Power Pole	S76E,	75.86' (to nail)
Power Pole	S74W,	97.31' (to nail)	9" Twin W. Birch	N67W,	78.40