

MAR 13 1998

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 47

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MARQUETTE
(County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 25W I-6
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Patricia D. Monley
REGISTER OF DEEDS *PM*

IRFP, 2 PAGE 38
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on JUNE 19TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6: Quarter Corner common to Sections 14 and 15.
1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:
6" Aspen N85W, 23 L 8" Spruce Pine S46E, 09 L

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE 12/8/97

1910: Charles Cummings, in Record of Surveys Book 1, pp. 121 - 123, indicates that he used the corner during a survey of T46N-R25W. No description of corner object or accessories given.

1941: Survey field notes from M.C.R.C. F.B. #712 (no pg. # given) indicate the corner as a set 1" Iron Pipe about 35' East of C/L Co. Rd. 553 near Contois House. No available bearing trees nearby.

1945: Survey field notes from M.C.R.C. F.B. #697, Pg. 72 indicate the corner as an Iron pipe. No accessories given.
(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6: 1997: No original corner evidence found. Found and accepted a 3 3/4" diameter D.N.R. Cap flush with ground and stamped to identify the corner by Paul Bressette P.S. #37270 in 1993. Found references as noted in Part C below. No nearby line calls were available to check. Distance North is 2623.65' and distance South is 2623.42'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6: 1997: Stamped "MCR 1997" on found D.N.R. Cap. Measured found references (trees were scribed) with distances to set d.h. nails:
8" J. Pine N10E, 32.42' (Bressette NBT) 6" J. Pine S11E, 21.81' (Bressette NBT)
7" R. Maple N36E, 55.10' (55.15' to meas. notch) (Bressette NBT)
C/L Co. Rd. 553 West, 73.8'
N.W. House Cor. S77E, 56.90' (Bressette Accessory) (Bressette must have taken bearing to S.W. Hse. Cor.; We measured S63E)
Green Steel Sign Post w/ Yellow Survey Marker Sign N90E, 1.1'
Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 12-8-97

I-6:

PART A CONTINUED:

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 15) indicates the corner as a 1" Iron Pipe about 35' East of Co. Rd. 553 near Contois' House. No accessories given.

1970: The corner is indicated on a survey map recorded by Allen Heikkinen P.S. #6517 in L. 287, Deeds Pg. 253; and L. 289, Deeds pp. 6, 8, and 10. No description of corner object or accessories given.

No Date: The corner is shown on M.C.R.C. road plans (State Proj. CS 52-48, Sheet 11) for Co. Rd. 553. No description of corner object or accessories given.

1989: Survey field notes from the files of Gerald W. Carlson, P.S. #24589, indicate the corner as a found 1" Pipe with mushroomed top.

Referenced by:

4" J. Pine	N11W,	12.77' (to nail)	6" J. Pine	N14E,	32.45' (to nail)
Utility Pole	N59E,	39.65' (to nail)	4" J. Pine	S07E,	21.88 (to nail)

1993: An LCRC recorded by Paul R. Bressette P.S. #37270 in L. 5, RC Pg. 379 indicates the corner as a found 1" Iron Pipe and witnesses by a previous surveyor. Replaced Iron Pipe with a D.N.R. Monument and witnessed. Corner falls 73.7' East of existing C/L of Co. Rd. 553. Measured found references with d.h. nails in side:

8" J. Pine	N17E,	32.46'	4" J. Pine	S04E,	21.83'
------------	-------	--------	------------	-------	--------

Established new references:

7" Red Maple	N44E,	55.1'	N.W. Cor. House	S65E,	57.29'
--------------	-------	-------	-----------------	-------	--------