

SURVEY & REMONUMENTATION

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 PM 1:55

corners in **COMMISSION**

Marquette <small>(County)</small>	Located In:	Corner Code #
	46N 25W	1-8
Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
Miscellaneous Property in Sec.	S ___ T ___ R ___	_____

Patricia A. Mackay
REGISTER OF DEEDS

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Bussone
DATE Sept 19, 1994

LIBER 1 PAGE 218
Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Michael Mileski, in a field survey on September 94, 1994

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

1-8; West One-Quarter Corner Section 23;

See back of form.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-8; West One-Quarter Corner Section 23;

Found 1" iron pipe consistent in form with previously recovered M.C.R.C. monumentation projecting 12" above ground within 2 feet of record M.C.R.C. distance to the northwest corner of section 23 (M.C.R.C. = 2626.89'; meas. = 2625.07'). No M.C.R.C. new bearing trees nor remains were recovered. For a detailed summary of the M.C.R.C. survey which established this corner and others refer to the Land Corner Recordation Certificate filed for corner 1-9.

State Plane Coordinates:
Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 578484.87211
X = 26143870.29409

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-8; West One-Quarter Corner Section 23;

See back of form.



Surveyed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Ref. to 712
for
restoration

A. Description of original monument and accessories and/or subsequent restoration:

I-8; West One-Quarter Corner Section 23;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 4 S04°E 12 lks. and a Spruce Pine 4 N71°W 08 lks.

This corner was initially remonumented with a 1" iron pipe and jack pine post on 19 December 1941 by the Marquette County Road Commission. This monument was moved 29.1 feet west and 39 feet north by the M.C.R.C. probably on 6 May 1942 for reasons that are unclear. Refer to M.C.R.C. field book 712 page 13.

As analysis of M.C.R.C. coordinate values obtained from M.C.R.C. field books 712 and 717 for the southwest corner section 23, west one-quarter corner section 23, and the northwest corner section 23 indicate that the M.C.R.C. intended to monument the west one-quarter corner of section 23 midway and on line between the immediate controlling corners to the north and south.

The M.C.R.C. noted the following new bearing trees:

- 7" Jack Pine N38°W 3.6'
- 5" Jack Pine N79°E 19.4'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8; West One-Quarter Corner Section 23;

Replaced found 1" iron pipe with 2" I.D. x 30 aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	NE/side	6" Jack Pine	S42°E	116.28'
Set 60d spike	SE/side	10" Jack Pine	S43°W	299.82'
Set 60d spike	N/side	8" Jack Pine	N89°W	280.05'
Set 60d spike	SW/side	9" Jack Pine	N62°W	382.82'
		Location Post	East	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".