

**SURVEY & REMONUMENTATION**

APR 28 1995

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 1994 DEC 29 PM 1:55

*Patricia B. Morley*  
 REGISTER OF DEEDS

For corners in	Located In:	Corner Code #
Marquette (County)	46N 25W	I-10
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**

*Larry J. Besone*  
 DATE Sept. 19, 1994

LIBER **1** PAGE **220**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Michael Mileski, in a field survey on September 94, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-10; West One-Quarter Corner Section 26;

See back of form.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10; West One-Quarter Corner Section 26;

Found 1" iron pipe projecting 12" above ground in agreement with the southeast M.C.R.C. new bearing tree which is presently alive (17" dia.) having lower face blaze and scribing evident and the southwest M.C.R.C. new bearing tree which is presently alive (12" dia.) having lower face blaze and scribing evident.

**State Plane Coordinates:**

Grid System - NAD 83  
 Zone Number - 2111 Michigan North  
 Units - International Feet  
 Y = 573231.00753  
 X = 26143817.22763

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10; West One-Quarter Corner Section 26;

See back of form.

Surveyed by Michael Mileski Date 21 Nov 1994  
 Surveyor's Michigan License No. 39091

95-6476  
P.O.  
S. C. B. M.

A. Description of original monument and accessories and/or subsequent restoration:

I-10; West One-Quarter Corner Section 26;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 4 N68°W 22 lks and a Spruce Pine 5 S19°E 08 lks.

This corner was remonumented with a 1" iron pipe and jack pine post on 27 May 1942 by the Marquette County Road Commission at a position intended to be on line between the southwest corner of section 35 and the northeast corner of section 27 at a distance proportional with the U.S. record. The Marquette County Road Commission intended to reestablish all U.S. corners lying between the southwest corner of section 35 and the northeast corner of section 27 on line between these two corners at equally spaced intervals. Refer to M.C.R.C. field book 717.

The M.C.R.C. noted the following new bearing trees:

12" Jack Pine S15°E 21.1'  
(Set 60d spike W/side S15°E 21.1')

7" Jack Pine S59°W 17.0'  
(Set 60d spike N/side S57°W 17.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-10; West One-Quarter Corner Section 26;

Replaced found 1" iron pipe with 2" I.D. x 30 aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	SE/side	5" Jack Pine	N66°E	82.97'
Set 60d spike	NE/side	6" Jack Pine	S54°E	80.83'
Set 60d spike	NW/side	9" Jack Pine	S29°W	59.48'
Set 60d spike	SW/side	11" Jack Pine	N37°W	64.10'
		Location Post	East	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".