

**SURVEY & REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN  
 RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

For corners in Marquette  
(County)

Located In: 46N 25W Corner Code #1-11

- |                                    |   |   |       |
|------------------------------------|---|---|-------|
| 1. Public Land Survey              | T | R | _____ |
|                                    | T | R | _____ |
|                                    | T | R | _____ |
|                                    | T | R | _____ |
| 2. Property Controlling in Section | S | T | R     |
|                                    | S | T | R     |
| 3. Miscellaneous Property in Sec.  | S | T | R     |
|                                    | S | T | R     |

*Patricia A. Mansley*  
 REGISTER OF DEEDS

**RATIFIED BY PEER GROUP**  
 P.A. 345 OF 1990

*Larry J. Burson*  
 DATE Sept 19, 1994

LIBER **1** PAGE **221**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Michael Mileski September 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-11; Southwest Corner Section 26;

See back of form.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11; Southwest Corner Section 26;

Found a 1" iron pipe consistent in form to previously recovered M.C.R.C. monumentation projecting 12 inches above ground harmoniously related with respect to alignment and distance to recovered Marquette County Road Commission corners to the north and south. Found no evidence of M.C.R.C. new bearing trees.

State Plane Coordinates:

Grid System - NAD 83  
 Zone Number - 2111 Michigan North  
 Units - International Feet  
 Y = 570599.29190  
 X = 26143786.25342

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11; Southwest Corner Section 26;

Replaced found 1" iron pipe with 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	E/side	8" Jack Pine	North	15.35'	(previous NBT)
Set 60d spike	S/side	10" Jack Pine	N79°E	54.03'	(upper & lower blazes, mkd. "NBT")
Set 60d spike	SE/side	9" Jack Pine	S41°W	12.62'	(previous NBT)
Set 60d spike	S/side	7" Jack Pine	N81°W	30.07'	(previous NBT)
		Location Post	North	1.5'	

Signed by *Michael Mileski* Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Ref 6476  
Geo  
Geo Sum

A. Description of original monument and accessories and/or subsequent restoration:

I-11; Southwest Corner Section 26;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 7 S56°W 08 lks.  
and a  
Spruce Pine 6 N17°E 06 lks.

This corner was remonumented with a 1" iron pipe and jack pine post on 27 May 1942 by the Marquette County Road Commission at a position intended to be on line between the southwest corner of section 35 and the northeast corner of section 27 at a distance proportional with the U.S. record. The Marquette County Road Commission intended to reestablish all U.S. corners lying between the southwest corner of section 35 and the northeast corner of section 27 on line between these two corners at equally spaced intervals. Refer to M.C.R.C. field book 717.

The M.C.R.C. noted the following new bearing trees:

- 6" Jack Pine N08°W 15.3'
- 4" Jack Pine S55°W 21.0'