

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

Patricia H. Moulton
REGISTER OF DEEDS

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE Sept 19, 1994

LIBER **1** PAGE **222**
Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
Marquette (County)	46N 25W	I-12
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Michael Mileski, in a field survey on September 94, 19____

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12; West One-Quarter Corner Section 35;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12; West One-Quarter Corner Section 35;
Found a 1" iron pipe projecting 16 inches above ground and within 3 feet of being midway and on line between the southwest corner of section 35 and the northwest corner of section 35.

State Plane Coordinates:
Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 567966.91412
X = 26143755.94361

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12; West One-Quarter Corner Section 35;
Replaced found 1" iron pipe with 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	W/side	8" Jack Pine	N26°E	52.54'
Set 60d spike	N/side	10" Jack Pine	S76°E	16.08'
Set 60d spike	S/side	7" Jack Pine	N76°W	19.33'
Set 60d spike	E/side	10" Jack Pine	N28°W	44.51'
		Location Post	North	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Q
64716
Dec
200
Jan

A. Description of original monument and accessories and/or subsequent restoration:

I-12; West One-Quarter Corner Section 35;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 7 S74°E 17 lks. and a Spruce Pine 7 N63°W 54 lks.

This corner was remonumented with a jack pine post by the Marquette County Road Commission on 27 May 1942 at a position intended to be midway and on line between the southwest corner of section 35 and the northwest corner of section 35. The M.C.R.C. did not note any new bearing trees. The Marquette County Road Commission intended to reestablish all U.S. corners lying between the southwest corner of section 35 and the northeast corner of section 27 on line between these two corners at equally spaced intervals. Refer to M.C.R.C. field book 717.