SURVEY & REMONUMENTATION

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

APR 2 8 1995

LAND CORNER RECORDATION CERTIFICATE ORANAISCIONI Filing Requirement of Act 74, Mich. P.A. 1970 1994 DEC 29 PM 1: 54

	MMISSION Filing Requ	irement of Act 74, Mich.	P.A. 1970	Patrice	ind.	Nonleys EEDS &
Marquette (County)	Located in:	Corner Code ##		REGIST	FER OF DE	EEDS /
Public Land Survey	T 46N R 25W	I-13 /	P.A. 345 OF 1	PEER GROI		·
•	TR			10 16611		•
2. Property Controlling in Section	T R S T R S T R		DATE Sent	LIBER	1	PAGE 20"
3. Miscellaneous	S T R S T R		Register o	f Deeds Stan	np & File	Number
Property in Sec.	2 <u> </u>					
4. Lot No, ,	Recorded Plat	7			.	
				BCDE	F G H	!
	•	;	2 {	┋ ─┼╴┋─┼╴	! — — 3 — .	╂╌┇╼┼╌┊╼
			3			
Michael Mileski	, in a field survey on	September 94	4	<u>′-+-</u> ₿- <u>+</u> -\$	}——— <u>-</u> 1¦0—	-1112-
do hereby certify that under re	quirements of P.A. 74, Michigan P.	A. of 1970, the corner points mer	ntioned 6		- - -	
n lines 1 and 2 above were i	n conformance with regulations a	and rules therefore as required	d in the	3-17-1-17	6 - [· · · 15 - · 	1 ¹ / ₄ 1 ³
	uctions of the United States Depa a Court of Law and/or that the corr					
above wère in conformance wi	th the rules of the Michigan Board	of Land Surveyors or by a Dec	ree of a	J-1-202	1	23 24
Court of Law; established, a expressed below:	re-established, monumented, re	-monumented, recovered, (or	und as			
•	orners, all in the same town a	and range may be recorde	الأسار		3-1-2/-	20-1-25-
on this certificate.	•	ma range, may be recorded	12	.]		
		•	13			35 - 30
A. Description of original	monument and accessories ar	nd/or subsequent restoration	on;	1000	1000	
I-13; Southwest C	Corner Section 35;	•	*	OF W	HCHIC M	Q.
See back of	form.			MICHA MILE PROFES SURV	TEL D. 1	EYOR *

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13; Southwest Corner Section 35;

Found no evidence of either U.S. or M.C.R.C. monumentation or accessories. Reestablished the southwest corner of section 35 at proportionate distance along an arc connecting the southeast corner of section 36 and the south one-quarter corner of section 34.

State Plane Coordinates

Grid System - NAD 83

Zone Number - 2111 Michigan North

Units - International Feet

= 26143724.77136

No. 3909

PROFESSIO

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13; Southwest Corner Section 35;

Set 3/4" x 24" iron rod with 3" aluminum cap appropriately stamped as to location.

W1:	SE Corner Concrete Light Pad	N10°E	105.34'
W2:	North Bolt of Light Pole mkd. with "X"	S44°E	117.67'
W3:	Top of Hydrant	S02°W	244,40'
W4:	NE Corner Concrete Light Pad	N54°W	28.29'

See sketch on back of form.

incall laviel by interest in the base of t	Date 21 Nov 1994
≡rveyor's Michigan License No. 39091	



Description of original monument and accessories and/or subsequent restoration:

I-13; Southwest Corner Section 35;

Originally established during U.S. Survey conducted by Wm. A. Burt, D.S. for Douglass Houghton, D.S. in 1844 and monumented with a wood post witnessed by a Spruce Pine 9 N24°E 25 lks. and a Spruce Pine 10 N72°W 20 lks.

And from the 1852 subdivision notes of T45N, R25W a Spruce Pine 15 S67°W 26lks. and a Spruce Pine 16 S30°E 15 lks.

During the course of a survey conducted by the Marquette County Road Commission in 1941 and described in M.C.R.C. field book 712 all U.S. corners lying between the south one-quarter corner of section 36 and the southwest corner of section 34 were considered lost. The south one-quarter corner of section 36 and the southwest corner of section 34 were both considered by the Marquette County Road Commission as legitimate U.S. corners and all intermediate standard corners except possibly the south one-quarter corner of section 35 were monumented with a 1" iron pipe and jack pine post at the appropriate proportioned position. Refer to M.C.R.C. field book 712 pages 8 & 9.

The M.C.R.C. noted the following new bearing trees as of 15 December 1941:

6" Jack Pine S48½ °E 34.2' 5" Jack Pine S50°W 19.5'