

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1999 DEC 22 AM 11:26

Patricia R. Monley
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T 46N R 25W _____ J-1 _____
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LIBER **R2** PAGE **213**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on December 1, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-1: North Quarter Corner of Section 2, T46N-R25W.
1999: Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-1: 1999: Corner position established by single proportionate measurement between the Northwest and Northeast corners of Section 2, on line between the South quarter corner and the Southeast corner of Section 35, T47N-R25W. Distances are 2662.41' West and 2662.41' East along the North Township Line of T46N-R25W to the Northwest and Northeast corners of Section 2. The South quarter corner of Section 35, T47N-R25W is West 19.34'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-1: 1999: Set a 3/4" by 3' long capped rebar with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.20' below ground. Referenced by:
34" Maple N78W 8.20' 8" Maple N89W 39.48'
10" Maple N43W 39.11' 11" Forked Maple S19W 39.97'

Green Steel Sign Post w/ Yellow Survey Marker Sign S85E 29.76'

Note: Bearing trees have d.h. measuring nails, and stamped B.T. Tags affixed.
Bk.12, Pg.150-151

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussard
DATE 11/1/99



Signed by Gerald W. Carlson Date 12-8-99
Surveyor's Michigan License No. 24589