

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

Patricia A. Mackay
REGISTER OF DEEDS

For corners in **COMMISSION**
Marquette
(County)

Located In: Corner Code #

46N 25W J-7

- | | | | | | | |
|------------------------------------|---|-------|---|-------|-------|-------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Busam
DATE Sept 19, 1994

LIBER **1** PAGE **223**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Michael Mileski September 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-7; North One-Quarter Corner Section 23;
See back of form.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7; North One-Quarter Corner Section 23;
Found a 1" iron pipe and maple post in agreement with the northeast M.C.R.C. new bearing tree which is presently alive (12" dia.) having healed mid-trunk blazes.

State Plane Coordinates:
Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 581131.35664
X = 26146536.69755

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7; North One-Quarter Corner Section 23;
Replaced found 1" iron pipe with 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.
Set 60d spike W/side 8" Red Maple N04°E 21.14'
Set 60d spike N/side 7" Red Oak S84°E 9.09'
Set 60d spike N/side 4" Red Oak S83°W 14.53'
Set 60d spike NE/side 7" Sugar Maple N43°W 27.15'
Location Post South 1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Ref 64716
92
Star Den

A. Description of original monument and accessories and/or subsequent restoration:

J-7; North One-Quarter Corner Section 23;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Sugar 6 N64°W 12 lks. and a Fir 5 N35°E 11 lks.

This corner was remonumented with a 1" iron pipe and squared maple post on 20 November 1944 by the Marquette County Road Commission at a position intended to be midway and on line between the northwest corner of section 23 and the northeast corner of section 23. Refer to M.C.R.C. field book 712 page 75.

The M.C.R.C. noted the following new bearing trees:

5" Maple N20°E 8.4'
(Set 60d spike SE/side N19°E 8.40')

4" Maple S65°E 6.4'