

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
 RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

Patricia A. Monloy
 REGISTER OF DEEDS

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
 DATE Sept 26, 1994

LIBER **1** PAGE **224**
 Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
Marquette (County)	46N 25W	J-9
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Michael Mileski, in a field survey on September 94, 1994

I do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

J-9; South One-quarter Corner Section 23;
 See back of form.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9; South One-quarter Corner Section 23;

Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished the south one-quarter corner of section 23 midway and on line between the southwest corner of section 23 and the southeast corner of section 23.

State Plane Coordinates:
 Grid System - NAD 83
 Zone Number - 2111 Michigan North
 Units - International Feet
 Y = 575859.48302
 X = 26146493.55936

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9; South One-quarter Corner Section 23;

Set 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 1/2" x 18" iron rod & cap	#39091	N45°E	45.00'
Set 60d spike SE/side	6" Jack Pine	S42°W	222.24'
Set 60d spike S/side	7" Jack Pine	N80°W	129.08'
Set 60d spike NE/side	5" Jack Pine	N22°W	290.46'
	Location Post	East	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Surveyed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

38 AF 6476
P 000
Sum

A. Description of original monument and accessories and/or subsequent restoration:

J-9; South One-quarter Corner Section 23;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 4 N18°E 9 lks.
and a
Spruce Pine 6 S85°W 20 lks.

This corner was remonumented with a 1" iron pipe and jack pine post on 21 June 1945 by the Marquette County Road Commission at a position intended to be midway and on line between the southwest corner of section 23 and the southeast corner of section 23. Refer to the M.C.R.C. field book 697 pages 67-69.

The M.C.R.C. noted the following new bearing trees:

- 4" Jack Pine S08°E 27.0'
- 4" Jack Pine S42°E 39.5'