

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

Patricia A. Manley
 REGISTER OF DEEDS

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussine
 DATE Sept 26, 1994

LIBER 1 PAGE 225
Register of Deeds Stamp & File Number

For corners in Marquette <small>(County)</small>	Located In:	Corner Code #
	46N 25W	J-11
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Michael Mileski, in a field survey on September 94, 1994

I do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

J-11; South One-quarter Corner Section 26;
 See back of form.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11; South One-quarter Corner Section 26;
 Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished the south one-quarter corner of section 26 midway and on line between the southwest corner of section 26 and the southeast corner of section 26.

State Plane Coordinates:
 Grid System - NAD 83
 Zone Number - 2111 Michigan North
 Units - International Feet
 Y = 570588.94985
 X = 26146425.51036

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11; South One-quarter Corner Section 26;
 See back of form.



Signed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

94-6476
D. G. B. B.

A. Description of original monument and accessories and/or subsequent restoration:

J-11-; South One-quarter Corner Section 26;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 8 S35°E 12 lks. and a Spruce Pine 6 N71°W 24 lks.

This corner was remonumented with a 1" iron pipe and jack pine post on 30 June 1942 by the Marquette County Road Commission at a position intended to be midway and on line between the southwest corner of section 26 and the southeast corner of section 26. Refer to M.C.R.C. field book 717.

The M.C.R.C. noted the following new bearing trees:

- 6" Jack Pine N18°W 6.2'
- 7" Jack Pine S12°W 27.6'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

J-11; South One-quarter Corner Section 26;

Set 3/4" x 24" iron rod with 3" aluminum cap appropriately stamped as to location.

Set 1/2" x 18" iron rod & cap #39091	S20°W	267.11'
Set 1/2" x 18" iron rod & cap #39091	S47°W	83.23'
Set 1/2" x 18" iron rod & cap #39091	N11°W	144.60'
Set 1/2" x 18" iron rod & cap #39091	N03°W	250.60'

All of the above iron rods set as accessories are located on the northerly side of the concretes base of runway light poles on the westerly side of the runway.