

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
 RECEIVED FOR RECORD

1994 DEC 29 PM 1:54

Patricia A. Mosley
 REGISTER OF DEEDS

for corners in **COMMISSION**

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code #
Public Land Survey	T <u>46N</u> R <u>25W</u>	<u>J-13</u> ✓
	T <u>45N</u> R <u>25W</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Beasome

DATE Sept 12, 1994

LIBER 1 PAGE 208
 Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Michael Mileski, in a field survey on September 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

J-13; South One-Quarter Corner Section 35;

See back of form.



Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13; South One-Quarter Corner Section 35;

Reestablished the south one-quarter corner of section 35 at proportionate distance along an arc connecting the southeast corner of section 36 and the south one-quarter corner of section 34.

State Plane Coordinates:

Grid System - NAD 83
 Zone Number - 2111 Michigan North
 Units - International Feet
 X = 565316.71018
 Y = 26146362.34501

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13; South One-Quarter Corner Section 35;

Set 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 1/2"x18" iron rod & cap #39091	N45°E	45.00'
Set 1/2"x18" iron rod & cap #39091	S45°E	45.00'
Set 1/2"x18" iron rod & cap #39091	S45°W	45.00'
Set 1/2"x18" iron rod & cap #39091	N45°W	45.00'
Location Post	North	1.5'

Recorded by Michael Mileski Date 21 Nov 1994
 Surveyor's Michigan License No. 39091

R# 64716
900
200 Rem

A. Description of original monument and accessories and/or subsequent restoration:

J-13; South One-Quarter Corner Section 35;

Originally established during U.S. Survey conducted by Wm. A. Burt, D.S. for Douglass Houghton, D.S. in 1844 and monumented with a wood post witnessed by a Spruce Pine 5 N36°E 38 lks.
and a
Spruce Pine 6 N59°W 37 lks.

During the course of a survey conducted by the Marquette County Road Commission in 1941 and described in M.C.R.C. field book 712 all U.S. corners lying between the south one-quarter corner of section 36 and the southwest corner of section 34 were considered lost. The south one-quarter corner of section 36 and the southwest corner of section 34 were both considered by the Marquette County Road Commission as legitimate U.S. corners and all intermediate standard corners except possibly the south one-quarter corner of section 35 were monumented with a 1" iron pipe and jack pine post at the appropriate proportioned position.