

SURVEY & REMONUMENTATION

MAR 13 1998

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 47

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 46N R 25W _____ K-6
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Patricia A. Munley
REGISTER OF DEEDS

LIBER **2** PAGE **41**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on DECEMBER 12TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-6: Quarter Corner common to Sections 13 and 14.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:
8" Sugar N82E, 26 L 10" Y. Birch S72W, 15 L

No further information available on corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6: 1997: No original corner evidence found. No other corner evidence found. Re-established position of Corner mid way and on line between the N.E. Corner of Section 14 and the S.E. Corner of Section 14. There were no nearby line calls available to check. distance North is 2628.01' and distance South is 2627.94' (As-staked distances).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6: 1997: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is on the East edge of dirt road, 0.5' below ground.

Established new references:

- 9" W. Pine N29E, 35.63' (to set d.h. nail)
- 6" J. Pine S82E, 29.89' (to set d.h. nail)
- 6" J. Pine S08E, 20.80' (to set d.h. nail)
- 13" W. Pine S78W, 54.92' (to set d.h. nail)

8"x9"x12" Magnetic Green Stone N84E, 12.3'

Green Steel Sign Post w/ Yellow Survey Marker Sign S79E, 5.0'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 13, Pg. 37-38

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Busome
DATE 12/15/97



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589