

**SURVEY & REMONUMENTATION**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

For corners in **COMMISSION**

Marquette  
(County)

Located In:

Corner Code #

1. Public Land Survey		46N 25W	K-7
	T	_____ R _____	_____
	T	_____ R _____	_____
	T	_____ R _____	_____
	T	_____ R _____	_____
2. Property Controlling in Section	S	_____ T _____ R _____	_____
	S	_____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S	_____ T _____ R _____	_____
	S	_____ T _____ R _____	_____

**RATIFIED BY PEER GROUP**  
P.A. 345 OF 1990

*Larry J. Bussine*  
DATE Sept 19, 1994

*Patricia A. Mowley*  
REGISTER OF DEEDS

LIBER **1** PAGE **226**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Michael Mileski in a field survey on September 94, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-7; Northeast Corner Section 23;

See back of form.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7; Northeast Corner Section 23;

Found a 1" iron pipe consistent in form with previously recovered M.C.R.C. monumentation and very nearly on the easterly prolongation of a line passing through the northwest corner of section 23 and the north one-quarter corner of section 23 both of which are legitimate M.C.R.C. corners and at such a distance as to place the north one-quarter corner of section 23 approximately 4 feet from its theoretical position.

State Plane Coordinates:

Grid System - NAD 83  
Zone Number - 2111 Michigan North  
Units - International Feet  
Y = 581153.46615  
X = 26149152.52588

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7; Northeast Corner Section 23;

Replaced found 1" iron pipe with 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	NW/side	4" Red Pine	N61°E	130.58'
Set 60d spike	NE/side	5" Jack Pine	S53°E	48.20'
Set 60d spike	S/side	4" Red Pine	N87°W	36.58'
Set 60d spike	E/side	5" Jack Pine	N13°W	120.26'
		Location Post	South	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Surveyed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

6476  
900  
200 Rem

A. Description of original monument and accessories and/or subsequent restoration:

**K-7; Northeast Corner Section 23;**

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Hemlock 12 N55°W 23 lks.  
and a  
Hemlock 14 S62°E 28 lks.

Per entry in Marquette County Road Commission field book 712 page 75 this corner was recovered as "an old fence corner". The M.C.R.C. did not note any new bearing trees.