

SURVEY & REMONUMENTATION

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 PM 1:55

COMMISSION

Patricia A. Manley
REGISTER OF DEEDS

For corners in Marquette (County)	Located In:	Corner Code #
	46N 25W	K-8
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussine
DATE Sept 26, 1994

LIBER **1** PAGE **227**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Michael Mileski September 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8; East One-quarter Corner Section 23;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Fir 6 S73°E 12 lks. and a Yellow Birch 18 N33°W 15lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8; East One-quarter Corner Section 23;

Found 1/2" iron rod in concrete. Found no evidence of U.S. bearing trees. Found monument is 11.4 feet south and 3.9 feet west of being midway and on line between appropriate controlling section corners.

State Plane Coordinates:

Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 578493.41172
X = 26149141.82790

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8; East One-quarter Corner Section 23;

See back of form.



Signed by *Michael Mileski* Date 21 Nov 1994

Surveyor's Michigan License No. 39091

*Blk 6476
Gas
See Plan*

A.C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8; East One-quarter Corner Section 23;

Replaced found 1/2" iron rod in concrete with 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	E/side	11" Red Oak	N16°E	248.16'
Set 60d spike	N/side	6" Red Oak	N54°E	121.69'
Set 60d spike	N/side	9" Red Oak	S89°E	91.40'
Set 60d spike	W/side	8" Red Oak	S09°E	347.31'
		Location Post	North	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".