

Q. 4. 64-76
P. 100
R. 100

A. Description of original monument and accessories and/or subsequent restoration:

K-9; Southeast Corner Section 23;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 6 S45°W 16 lks and a Spruce Pine 4 N34°E 22 lks.

This corner was remonumented with an iron pipe (size unknown) and jack pine post on 20 June 1945 by the Marquette County Road Commission at a position intended to be on line between the southwest corner of section 23 and the south one-quarter corner of section 24 at a distance of 2640.0 feet westerly of the south one-quarter corner of section 24. Refer to M.C.R.C. field book 697 pages 67-69.

The M.C.R.C. noted the following new bearing trees:

- Jack Pine 4" S63½°E 68.4'
- Jack Pine 3" N33°E 118.6'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-9; Southeast Corner Section 23;

Replaced found 1" iron pipe with 2" I.D. x 30 aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	N/side	6" Red Pine	N40°E	24.10'
Set 60d spike	E/side	7" Red Pine	S19°E	43.96'
Set 60d spike	S/side	8" Jack Pine	S43°W	68.09'
Set 60d spike	E/side	5" Red Pine	N51°W	25.78'
		Location Post	East	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".