

**SURVEY & REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN  
 RECEIVED FOR RECORD

1994 DEC 29 PM 1:56

For corners in

Marquette  
(County)

Located In:

Corner Code #

1. Public Land Survey		<u>46N</u> <u>25W</u>	<u>K-10</u>
	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

*Patricia A. Mosley*  
 REGISTER OF DEEDS

**RATIFIED BY PEER GROUP**  
 P.A. 345 OF 1990

*Harry J. Bussard*  
 DATE Sept 26, 1994

LIBER **1** PAGE **229**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Michael Mileski in a field survey on September 94, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-10; East One-quarter Corner Section 26;

See back of form.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10; East One-quarter Corner Section 26;

Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished corner midway and on line between the northeast corner of section 26 and the southeast corner of section 26.

State Plane Coordinates:

Grid System - NAD 83  
 Zone Number - 2111 Michigan North  
 Units - International Feet  
 Y = 573217.42537  
 X = 26149101.84179

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10; East One-quarter Corner Section 26;

Set 2" I.D. x 30" aluminum pipe with 3" aluminum cap appropriately stamped as to location.

Set 60d spike	E/side	10" Jack Pine	N10°E	52.40'
Set 60d spike	S/side	4" Jack Pine	N74°E	23.84'
Set 60d spike	S/side	6" Jack Pine	S79°W	95.19'
Set 60d spike	SW/side	8" Jack Pine	N43°W	75.19'
		Location Post	North	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

signed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Plat 6476  
900  
Joe Jem

A. Description of original monument and accessories and/or subsequent restoration:

K-10; East One-quarter Corner Section 26;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 6 S42°E 40 lks. and a Spruce Pine 4 S88°W 16 lks.

Per Marquette County Road Commission corner index sheet this corner is indicated as monumented.