

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 29 PM 1:56

Patricia A. Moulton
REGISTER OF DEEDS

For corners in
Marquette
(County)

Located In: Corner Code #

1. Public Land Survey	46N 25W	K-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Besome
DATE Sept 26, 1994

LIBER **1** PAGE **230**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Michael Mileski September 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-11; Southeast Corner Section 26;

See back of form.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11; Southeast Corner Section 26;

Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished the southeast corner of section 26 by double proportioning to the U.S. record using the NE corner of section 26, NE corner section 36, SE corner section 35, and the SW corner section 26 as control.

State Plane Coordinates:

Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 570578.60780
X = 26149064.76710

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11; Southeast Corner Section 26;

Set 3/4" x 24" iron rod with 3" aluminum cap appropriately stamped as to location. Corner position falls in an asphalt parking lot.

SE Cor. Bldg. #541	N37°E	192.42'
NE Cor. Bldg. #249	S42°E	263.14'
NW Cor. Bldg. #249	S12°W	199.63'
Set 60d spike E/side 13"Scotch Pine	S25°W	112.34'

Signed by *Michael Mileski* Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Ref 6476
of
D. W. Dim

A. Description of original monument and accessories and/or subsequent restoration:

K-11; Southeast Corner Section 26;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 4 S54°W 11 lks. and a Spruce Pine 6 N83°E 21 lks.

This corner was remonumented with a 1" iron pipe and jack pine post by the Marquette County Road Commission on 30 June 1942 at a position intended to be S89° 35'E a distance of 5279.6 feet (U.S. = 5293.20 feet) from the southwest corner of section 26. According to M.C.R.C. field notes contained in M.C.R.C. field book 717 a line was produced from the southwest corner of section 26 on a bearing of S89° 35'E without any angle points for a distance of 5279.6 feet to the southeast corner of section 26. The M.C.R.C. did not note any new bearing trees.