

**SURVEY & REMONUMENTATION**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1994 DEC 29 PM 1:54

*Patricia A. M... 200*  
REGISTER OF DEEDS

or corners in <b>Marquette</b> (County)	Located In:	Corner Code #
Public Land Survey	T 46N R 25W T 45N R 25W T _____ R _____ T _____ R _____	<u>K-13</u> ✓ K-1
Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	
Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	

**RATIFIED BY PEER GROUP P.A. 345 OF 1990**

*Larry J. Bussone*

DATE Sept 12, 1994

LIBER 1 PAGE 209  
Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

**Michael Mileski** September 94

in a field survey on \_\_\_\_\_, 19\_\_\_\_, I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

K-13; Southeast Corner Section 35;

See back of form.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13; Southeast Corner Section 35;

Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished the southwest corner of section 36 at proportionate distance along an arc connecting the southeast corner of section 36 and the south one-quarter corner of section 34.


State Plane Coordinates:

Grid System - NAD 83  
Zone Number - 2111 Michigan North  
Units - International Feet  
Y = 565300.92268  
X = 26148999.92024

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13; Southeast Corner Section 35;

See back of form.



Red by Michael Mileski Date 21 Nov 1994  
Surveyor's Michigan License No. 39091

*Plt 6476  
900  
Lab Lem*

A. Description of original monument and accessories and/or subsequent restoration:

K-13; Southeast Corner Section 35;

Originally established during U.S. Survey conducted by Wm. A. Burt, D.S. for Douglass Houghton, D.S. in 1844 and monumented with a wood post witnessed by a Spruce Pine 8 N74°E 38 lks. and a Spruce Pine 8 N48°W 25 lks.

And from the 1852 subdivision notes of T45N, R25W a Spruce Pine 12 S31°W 11 lks. and a Spruce Pine 14 S65°E 14 lks.

During the course of a survey conducted by the Marquette Road Commission in 1941 and described in M.C.R.C. field book 712 all U.S. corners lying between the south one-quarter corner of Section 36 and the southwest corner of section 34 were considered lost. The south one-quarter corner of section 36 and the southwest corner of section 34 were both considered by the Marquette County Road Commission as legitimate U.S. corners and all intermediate standard corners except possibly the south one-quarter corner of section 35 were monumented with a 1" iron pipe and jack pine post at the appropriate proportioned position. Refer to M.C.R.C. field book 712 page 9 for diagram.

The M.C.R.C. noted the following new bearing trees as of 15 December 1941:

- 9" Jack Pine S35°E 34.6'
- 6" Dry Jack Pine Stub S85°W 83.9'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-13; Southeast Corner Section 35;

Set 3/4" x 24" iron rod with 3" aluminum cap proportionally along an arc correcting the southeast corner of section 36 and the south one-quarter corner section 34.

N21°E	SW Corner of Garage		171.89'
N62°E	Set 1/2" x 18" Iron Rod & Cap	#39091	46.65'
S62°W	Set 1/2" x 18" Iron Rod & Cap	#39091	129.31'
N53°W	SE'ly Corner Warehouse Bldg.		108.44'
N12°W	SE Corner Quonset Bldg.		274.71'