

1999 DEC 22 AM 11:26

*Patricia A. Manley*  
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 46N R 25W \_\_\_\_\_ L-1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LIBER **R2** PAGE **215**

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on December 2, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
L-1: North Quarter Corner of Section 1, T46N-R25W.  
1999: Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1: 1999: Corner position established by single proportionate measurement between the Northwest and Northeast corners of Section 1 on line between the South quarter corner and the Southeast corner of Section 36, T47N-R25W. Distances are 2619.63' West and 2619.63' East along the North Township Line of T46N-R25W to the Northwest and Northeast corners of Section 1. The South quarter corner of Section 36, T47N-R25W is West 4.62'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.30' above ground. Referenced by:  
5" Maple S66W, 4.86' 6" White Birch N40W, 5.41'  
7" Maple N40E, 13.00' 10" White Birch S56E, 8.73'

Green Steel Sign Post w/ Yellow Survey Marker Sign Due North, 3.00'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.  
Bk.12, Pg. 152-153

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

DATE 11/1/99



Signed by Gerald W. Carlson Date 12-8-99  
Surveyor's Michigan License No. 24589