

**SURVEY & REMONUMENTATION**

MAR 13 1998

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 48

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Patricia R. Mackay*  
REGISTER OF DEEDS

For corners in

MARQUETTE  
(County)

Located In:

Corner Code #

1. Public Land Survey      T 46N R 25W      L-5  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

LIBER      **2** PAGE **50**  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on DECEMBER 18TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5											●	
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

L-5: Quarter Corner common to Sections 12 and 13.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:

15" Sugar      S48E,      43 L      7" Sugar      N17E,      28 L

No further information available on corner.

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**

*Larry J. Bussine*  
DATE 12/15/97

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-5: 1997: No original corner evidence found. No other corner evidence found. Re-established position of Corner mid way and on line between the S.W. Corner of Section 12 and the S.E. Corner of Section 12. There were no nearby line calls available to check. Distance West is 2656.79' and distance East is 2656.79' (calculated distances).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-5: 1997: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.2' above ground.

Established new references (measures are to set d.h. nails):

- 12" Oak      N86E,      11.28'
- 11" Oak      S35E,      14.38'
- 19" Oak      S08E,      19.45'
- 11" Oak      N22W,      19.36'

Green Steel Sign Post w/ Yellow Survey Marker Sign      S54E,      3.6'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.  
Bk. 14, Pg. 59-60



Signed by Gerald W. Carlson      Date 12-18-97