

SURVEY & REMONUMENTATION

MAR 13 1998

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 DEC 26 PM 12: 48

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>46N</u> R <u>25W</u> | <u>L-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Patricia L. Manberg
REGISTER OF DEEDS

LIBER

2 PAGE 51

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on DECEMBER 17TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7: Quarter Corner common to Sections 13 and 24.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:

18" Cedar N26E, 16 L 6" Fir S54W, 28 L

1944: Survey field notes from M.C.R.C. F.B. #712 (no pg. # given) indicate the corner as set 1" Iron Pipe. It is noted that the corner was set as closely as possible with the information on hand, and that it was not witnessed due to the uncertainty of its exact location.

No Date: The M.C.R.C. Government Corner Index Book (F.B. #647 - Sec. 24) indicates the corner as a 1" Iron Pipe. No description of corner object or accessories given.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE 12/15/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7: 1997: No original corner evidence found. No other corner evidence found. Re-established position of Corner mid way on line between the S.W. Corner of Section 13 and the S.E. Corner of Section 13. Checked Line Call: West, 5.47 chains [361.02'] stream, 9 L [5.94'] course N.E. in deep ravine. Measured Call: West, 360' to stream. Distance West is 2656.19' and Distance East is 2656.19' (calculated distances).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7: 1997: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.3' above ground.

Established new references (to set d.h. nails):

- | | | |
|------------|-------|--------|
| 12" Spruce | N62W, | 48.23' |
| 23" Cedar | N16W, | 25.49' |
| 19" Cedar | N45E, | 36.46' |
| 12" Cedar | S50E, | 54.18' |

Green Steel Sign Post w/ Yellow Survey Marker Sign S60E, 2.3'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.
Bk. 14, Pg.55-56



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589