

**SURVEY &
REMONUMENTATION**

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 29 PM 1:56

Patricia L. Myles
REGISTER OF DEEDS

For corners in

Marquette (County)	Located In:	Corner Code #
Public Land Survey	T <u>46N</u> R <u>25W</u>	L-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussard
DATE Sept 26, 1994

LIBER **1** PAGE **232**
Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Michael Mileski, in a field survey on September, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

L-11; North One-quarter Corner Section 36;

See back of form.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11; North One-quarter Corner Section 36;

Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished corner midway and on line between the northwest corner of section 36 and the northeast corner of section 36.

State Plane Coordinates:

Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 570563.65192
X = 26151697.42012

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11; North One-quarter Corner Section 36;

Set 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	E/side	5" Scotch Pine	N01°E	84.86'
Set 60d spike	SW/side	20" Jack Pine	S40°E	93.26'
Set 60d spike	SE/side	7" Scotch Pine	S38°E	4.62'
Set 60d spike	NE/side	5" Scotch Pine	N52°W	44.62'
		Location Post	North	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Recorded by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Ref 6476
900
300 Ben

A. Description of original monument and accessories and/or subsequent restoration:

L-11; North One-quarter Corner Section 36;

Originally established during U.S. Survey conducted by Wm. Ives, D.S. for Douglass Houghton, D.S. in 1845 and monumented with a wood post witnessed by a Spruce Pine 6 N17°E 11 lks. and a Spruce Pine 4 S28°W 10 lks.

This corner was remonumented with a 1" iron pipe and jack pine post on 27 Oct 1944 by the Marquette County Road Commission at a position intended to be N89° 26'W at a distance of 2640.0 feet from the northeast corner of section 36. Refer to M.C.R.C. field book 712 pages 59. Per M.C.R.C. field notes the south township line bears N89° 27'W: Refer to M.C.R.C. field book 712 page 9.

The M.C.R.C. noted the following new bearing trees:

- 5" Jack Pine S54°E 85.8'
- 9" Jack Pine S05°W 113.2'