

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
 RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

Patricia L. Mearns
 REGISTER OF DEEDS

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
 DATE Sept. 12, 1994

LIBER 1 PAGE 210
Register of Deeds Stamp & File Number

For corners in

Marquette
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|---------------|
| 1. Public Land Survey | T <u>46N</u> R <u>25W</u> | <u>L-13</u> ✓ |
| | T <u>45N</u> R <u>25W</u> | <u>L-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Michael Mileski, in a field survey on September, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 L-13; South One-Quarter Corner Section 36;
 See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 L-13; South One-Quarter Corner Section 36;
 See back of form.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-13; South One-Quarter Corner Section 36;
 See back of form.



Signed by *Michael Mileski* Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Set 6476
Geo
2003

A. Description of original monument and accessories and/or subsequent restoration:

L-13; South One-Quarter Corner Section 36;

Originally established during U.S. Survey conducted by Wm. A. Burt, D.S. for Douglass Houghton, D.S. in 1844 and monumented with a wood post witnessed by a Spruce Pine 14 S14°E 30 lks. and a Tamarack 5 N30°W 32 lks.

The U.S. field notes state that this corner is located in a stream.

On 12 December 1941 the Marquette County Road Commission recovered an "iron pipe in creek" with fences running north and east. M.C.R.C. field notes state that the iron pipe was in the "correct location" and was regarded as a legitimate U.S. corner. Refer to M.C.R.C. field book 712 pages 7 & 9.

The M.C.R.C. did not note any new bearing trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

L-13; South One-Quarter Corner Section 36;

Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Corner position proportioned along an arc connecting the southeast corner of section 36 and the south one-quarter corner of section 34. Corner position falls in the center of a 20' wide stream and is in reasonable agreement with U.S. stream calls to the east and west. Corner position is 2 feet north of a fence to the east and 8 feet east of a fence running north and south into both sections 36 and 1.

State Plane Coordinates
 For S ¼ Cor. 36-46-25
 Grid System - NAD 83
 Zone Number - 2111 Michigan North
 Units - International Feet
 Y = 565285.47518
 X = 26151637.49703

State Plane Coordinates
 For Witness Corner
 Grid System - NAD 83
 Zone Number - 2111 Michigan North
 Units - International Feet
 Y = 565284.61720
 X = 26151787.47178

C. Description of monument and accessories established to perpetuate locating the position of the corner.

L-13; South One-Quarter Corner Section 36;

Established Witness Corner monumented with a 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location at a distance of 150.00' easterly of the south one-quarter corner section 36 and on line with the southeast corner section 36.

Set 60d spike	S/side	9" Jack Pine	S68°E	31.58'
Set 60d spike	W/side	6" Red Maple	S14°E	46.48'
Set 60d spike	NW/side	14" Jack Pine	S58°W	76.51'
Set 60d spike	NE/side	15" Tamarack	N39°W	63.17'
		Location Post	N40°E	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".