

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO.: 1-358

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: MARQUETTE (County), Located In: (Town/Range), Corner Code #. Includes entries for Public Land Survey and Property Controlling in Section.

1993 DEC 29 AM 10:33
RECEIVED FOR RECORD
MARQUETTE COUNTY MICHIGAN
LIBER 1 PAGE 55
Register of Deeds Stamp File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, GERALD W. CARLSON, in a field survey on Thursday, December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13, containing numerical values for survey points.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13: Section Corner common to Section 31, T47N-R24W; Section 6, T46N-R24W; Section 1, T46N-R25W; and Section 36 T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 16" Hemlock S85W, 22 l; 26" Hemlock N18E, 54 l. 1980 - G. Carlson set a 4" diameter by 36" concrete monument from evidence of the remains of a wood post at the correct bearing and distance N85E 22 l from a Hemlock stump. This position also checks with the remains of the Hemlock line tree 840 ft. to the East. Referenced by 12" Maple, S16W, 23.82 ft.; 8" Maple, S80E, 18.44 ft.; 4" Tw. Maple, N45E, 22.03 ft.; 8" Tw. Maple, N71W, 37.06 ft. L1 RC, Pg. 21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found G. Carlson concrete monument as set in 1980. Replaced with a Marquette County Survey Monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced concrete monument with 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in: 14" Maple S16W 23.78 ft. Carlson NBT; 8" Maple S80E 18.48 ft. Carlson NBT; 4" Maple N45E 22.03 ft. Carlson NBT; 10" Twin Maple N71W 37.00 ft. Carlson NBT. Monument is 0.8 ft. above ground. Bk. 3, Pg. 156

Signed by Gerald W. Carlson
Surveyor's Michigan License No. 24589

Date 12-23-93

