

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
RECEIVED FOR RECORD
1994 DEC 29 PM 1:56

*Patricia A. M...
REGISTER OF DEEDS*

For corners in
Marquette
(County)

Located In: Corner Code #

1. Public Land Survey	T	46N	R	25W	M-11 ✓
	T	46N	R	24W	A-11
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bassone
DATE Sept 26, 1994

LIBER 1 PAGE 233
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Michael Mileski September 94

I, _____, In a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-11; Northeast Corner Section 36;

See back of form.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11; Northeast Corner Section 36;

Found a 1" iron pipe projecting 10" above ground in agreement with the northeast M.C.R.C. new bearing tree which is presently alive (16" dia.) having partially healed mid-trunk blaze with scribing evident.

State Plane Coordinates:

Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 570548.69604
X = 26154330.07337

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11; Northeast Corner Section 36;

Replaced found 1" iron pipe with 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 60d spike	NW/side	6" Jack Pine	N46°E	75.42'
Set 60d spike	SW/side	4" Red Maple	S34°E	42.90'
Set 60d spike	SW/side	11" Red Oak	N50°W	83.35'
Set 60d spike	W/side	8" Red Oak	N02°W	74.97'
		Location Post	North	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

*Revised
9/20/76
Geo. B. Burt*

A. Description of original monument and accessories and/or subsequent restoration:

M-11; Northeast Corner Section 36;

Originally established during U.S. Survey conducted by Wm. A. Burt, D.S. for Douglass Houghton, D.S. in 1844 and monumented with a wood post witnessed by a White Birch 7 S25°E 18 lks.
and an
Aspen 10 N20°W 32 lks.

And from the 1845 subdivision notes of T46N, R24W, a Yellow Pine 24 S76°E 21 lks.
and an
Aspen 9 N35°E 29 lks.

This corner was remonumented with a 1" iron pipe and jack pine post on 27 October 1944 by the Marquette County Road Commission at a position intended to be S89°46'W a distance of 5146.5 feet (U.S. = 5118.96 feet) from the northeast corner of section 31, T46N, R24W. According to the M.C.R.C. field notes contained in M.C.R.C. field book 712 on pages 58-59 a line was produced on a bearing of S89°46'W from the northeast corner of section 31, T46N, R24W without any angle points for a distance of 5146.5 feet to the northeast corner of section 36, T46N, R25W. The north one-quarter corner of section 31, T46N, R24W was reestablished on this line at a distance of approximately 2637 feet (U.S. - 2640 feet) westerly of the northeast corner of section 31, T46N, R24W.

While U.S. topographic call considerations probably influenced the M.C.R.C.'s placement of the north one-quarter corner of section 31, T46N, R24W, the reasoning used by the M.C.R.C. to determine the position of the northeast corner of section 36, T46N, R25W is unclear.

For the northeast corner of section 36, T46N, R25W, the M.C.R.C. noted the following new bearing trees:

7" Jack Pine	N21°W	46.7'
10" Jack Pine	N70°E	63.9'
(Set 60d spike S/side	N70°E	63.9')