

SURVEY & REMONUMENTATION

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

APR 28 1995

1994 DEC 29 PM 1:56

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Patricia A. Mankley
REGISTER OF DEEDS

For corners in Marquette (County) Located In: Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>25W</u>	<u>M-12</u> ✓
	T <u>46N</u> R <u>24W</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bessine
DATE Sept 26 1994

LIBER **1** PAGE **234**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Michael Mileski in a field survey on September 94, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:
M-12; East One-Quarter Corner Section 36;
See back of form.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-12; East One-quarter Corner Section 36;

Corner is now located in a flooded area. Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished the east one-quarter corner of section 36 midway and on line between the southeast corner of section 36 and the northeast corner of section 36.

State Plane Coordinates
For E 1/4 Cor. 36-46-25
Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 567909.54242
X = 26154302.57443

State Plane Coordinates
For Witness Corner
Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 568226.47703
X = 26154305.87655

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12; East One-quarter Corner Section 36;
See back of form.



Signed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

Q14 6476
Geo
Geo
Geo

A. Description of original monument and accessories and/or subsequent restoration:

M-12; East One-quarter Corner Section 36;

Originally established during U.S. Survey conducted by Wm. A. Burt, D.S. for Douglass Houghton, D.S. in 1844 and monumented with a wood post witnessed by a Fir 12 S45°E 14 lks. and a White Pine 16 N55°W 12 lks.

Per entry in Marquette County Road Commission field book 712 page 34 this corner was recovered on 1 July 1942 as an "old fence corner in swamp, about 10' south of creek. This fence corner has been set correctly at E¼ corner of sec. 36-46-25 according to the U.S. field notes." Apparently the rationale used by the M.C.R.C. to state that the fence corner is in the corner location according to the U.S. field notes is that per the U.S. record the corner is 12 links (7.92 feet) south of the stream. The M.C.R.C. field notes do not indicate that any U.S. bearing tree evidence was recovered. The M.C.R.C. did not note any new bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12; East One-quarter Corner Section 36;

Not practical to monument the east one-quarter corner of section 36, T46N, R25W at the computed single proportioned position. Set 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) on section line at a ground distance of 317.00 feet northerly of the east one-quarter corner position for a witness corner. Established the following accessories for the witness corner:

Set 60d spike	E/side	33" White Pine	N08°E	31.02'
Set 60d spike	SE/side	7" Red Maple	S62°W	80.67'
Set 60d spike	S/side	5" Spruce	S82°W	20.79'
Set 60d spike	W/side	6" Red Maple	N15°W	64.29'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".