

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY


T 46 N R 26 W

DESCRIPTION OF CORNER Section corner for sections ^{20/21} 29/28

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/22/70

WITNESSES TO CORNER..... 7" J. Pine (S 20) (NBT) N 53° W, 46.5'



12" J. Pine (NBT) North, 1.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set by single proportionate measurement N and S between Escanaba River south and line tree north. Departure was determined from occupation to east. Old blaze line N and S and east. Other old blazes near-by. No evidence of original corner found.

SURVEYOR'S SEAL

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

11/20/70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68